



Technical drawing of a square table top with a central circular hole. The drawing includes dimensions for the square frame (5000 mm side), the central hole (3000 mm diameter), and various offsets (180 mm, 360 mm, 420 mm, 4640 mm). It also shows a cross-section 'A-A' and a detail 'a' of the corner joint. The table is labeled 'PROFIL NARAŽNY C14 L=11,00 m'.



WYMIARY W mm



Technical drawing of a trench cross-section. The drawing shows a trench with a width of 5000 mm and a depth of 4980 mm. The trench is lined with a material labeled "OBUDOWA WYKOPU Z GRODZIC G62 L=11,0 m". The bottom of the trench is at an elevation of 73,99. The top of the trench is at an elevation of 84,75. The drawing also shows a cross-section of a structure within the trench, with dimensions 500, 1500, 4020, and 5520. The structure is made of HEB 360 (L=5,00 m) and I c 200 (L=0,40 m). The drawing includes a load of 10 kPa on the top surface and a load of 78,97 on the bottom surface. The drawing is labeled with "B" and "T. ISTN.".

WYKAZ STALI PROFILOWEJ						
NUMER	PROFIL	DŁUGOŚĆ	IŁOŚĆ	MASA [kg]		
		m	szt.	1 mb	1 SZT.	RAZEM
1	GRODZICA G62	11,00	52	62,0	682,0	35464,0
2	PROFIL C14	11,00	4	142,0	1562,0	6248,0
3	Id HEB 360	5,00	4	142,0	710,0	2840,0
4	Id HEB 360	0,595	4	142,0	84,5	338,0
5	Ic 200	0,40	8	25,3	10,1	81,0
MASA ŁĄCZNA				kg	44971	

STAL PROFILOWA S235
ODWODNIENIE WYKOPU WG ODREBNEGO OPRACOWANIA

Inwestor:  Zarząd Powiatu Wołomińskiego ul. Prądzynskiego 3 05-200 Wołomin		Jednostka Projektowa: Mareckie Inwestycje Miejskie Sp. z o.o. Al. Marszałka J. Piłsudskiego 96 lok. 2 05-270 Marki	
Zadanie:	Rozbudowa ulicy Kościuszki i Sosnowej		
Obiekt:	Oczyszczalnia wód deszczowych OWD IA.3 - ul. Kościuszki		
Nazwa rysunku:	Szalowanie wykopu dla pompowni P1-IA.3		
	Tytuł, imię i nazwisko:	Nr uprawnień:	Podpis:
Projektował:	inż. Andrzej Rodziewicz	St-316/81	
Opracował:	techn. Janina Pawlak	—	
Sprawdził:			
Stadium: PW	Branża: konstrukcyjna	Data: 05.2015	Skala: 1:50
			Nr rys.: 2